

Storm Sewer Unit Cost Rates

Pipe Diameter (in)	Unit Cost Rate (\$/ln ft)
24	\$550.00
30	\$590.00
36	\$640.00
42	\$680.00
48	\$850.00
54	\$880.00
60	\$930.00
66	\$1,000.00
72	\$1,090.00
78	\$1,200.00
84	\$1,310.00
96	\$1,470.00
108	\$1,640.00
120	\$3,190.00
132	\$2,150.00
144	\$2,410.00
156	\$2,670.00
168	\$4,740.00
180	\$5,620.00
192	\$5,820.00
252	\$6,040.00
264	\$6,820.00

Notes:

1. Unit Cost Rates were developed based on City of Houston Bid Tabs for storm sewer projects constructed in 2020-2022
2. Unit Cost Rates include the following:
 - Removal of existing pipe and pavement
 - Storm sewer pipe
 - Manholes
 - Inlets
 - Replacement of pavement
 - Groundwater control
 - Storm Water Pollution Prevention Plan (SW3P)
 - Trench safety
 - Traffic control
 - Mobilization
 - Engineering and contingency (20%)
3. Unit Cost Rates do not include the following:
 - Relocation of existing utilities
 - Acquisition of additional right-of-way